

REQUEST FOR BOARD ACTION

**HENDERSON COUNTY
BOARD OF COMMISSIONERS**

MEETING DATE: October 21, 2015
SUBJECT: Henderson County Public Schools Long Term Capital Request
PRESENTER: Chad Roberson, Architect
ATTACHMENTS: Yes

SUMMARY OF REQUEST:

At the Board's October 5, 2015 meeting, Henderson County Board of Education Chairman Ervin Bazzle presented the Board's Long Term Capital Request to the Board of Commissioners. Following that presentation, the Board scheduled Architect Chad Roberson for today's meeting, to present a detailed analysis and justification for the request to the Board.

BOARD ACTION REQUESTED:

The Board is requested to hear the presentation, and direct staff accordingly.

Suggested Motion(s):

No motion suggested.

Henderson County Public Schools where tomorrow begins 

Blue Ridge
COMMUNITY COLLEGE

HENDERSON COUNTY - North Carolina -



CLARK NEXSEN

EARLY COLLEGE HIGH SCHOOL & CAREER ACADEMY



CAREER ACADEMY VISION

- Hands-on Career and Technical Training
- Study with highly qualified Community College Instructors
- Study in professional Community College labs
- Seamless transition: High school to Post Secondary Training

BUILDING VISION

- 250 Early College High School Students
- 250 Career Academy Students
- Separate schools sharing common spaces, including Kitchen/Dining, Multipurpose, and Media.
- Early College High School continues successful partnership with BRCC.
- Career Academy Students gain access to the instructors and facilities of the College.



EXISTING SITE PLAN



CURRENT MASTER PLAN



PROPOSED BUILDING LOCATION

Conceptual Budgeting - Early College High School & Career Center

Clear and Prepare the Site	1.0	acres	@	\$ 200,000.00		\$ 200,000.00
Construct New Buildings	50,000	sf	@	\$ 198.00		\$ 9,900,000.00
Sitework	1	acres	@	\$ 200,000.00		\$ 200,000.00
Escalation-Assumed construction complete by 6/2018	25.0	month	@	.37% per month	9.250%	\$ 934,250.00

Sub total						\$ 11,234,250.00
Overhead and Profit					6.0%	\$ 674,055.00
Sub total						\$ 11,908,305.00
Bonds and insurance					1.5%	\$ 178,624.58
Grand Total Construction costs						\$ 12,086,929.58

Owner Contingency					8.0%	\$ 966,954.37
Soft Costs(AE fees, CM pre-con fee, survey, permitting, geotech, special inspector, material testing agent, Air Monitoring etc.)					12.0%	\$ 1,450,431.55
Commissioning agent					1.0%	\$ 120,869.30
Furniture, fixture, equipment	50,000	sf	@	\$ 10.00		\$ 500,000.00
Technology/ Equipment						\$ 600,000.00
Total Project costs						\$ 15,725,184.79

EDNEYVILLE
ELEMENTARY

21ST CENTURY



OVERALL GOALS:

- Minimize length of construction
- Thoughtfully stage the work
- Maintain continuity of programs
- Minimize number of moves

- Work with existing topography
- Integrate vehicular access and parking

- Optimize program adjacencies
- Meet 21st century demands





FACILITIES

PROGRAMMING

OPTIONS

BUDGET SUMMARY



FACILITIES



II. FEASIBILITY ANALYSIS

II-A. FEASIBILITY ANALYSIS - BUILDING

A. Educational Program Adequacy - Typical size of classrooms and other functional spaces compared to the N.C. Public School Facility Guidelines.

- o 85% to 100% of current guidelines = 6
- o 75% to 85% of current guidelines = 3
- o Less than 75% of guidelines or classrooms less than 600 sq.ft. = 0

0

B. Historical or Architectural Significance

- o Listed on the National Historic Register or of significant regional architectural interest = 2
- o Strong local historic interest or sentiment or an example of good school design = 1
- o No particular historical value or architectural interest = 0

0

C. Safety and Code Compliance

- o Generally meets building code requirements (1978 or 1991 code) = 4
- o Needs some modifications in order to meet current bldg. code requirements = 2
- o Needs substantial modifications to meet current building code requirements = 0

2

D. Relationship to Other Buildings on Site (including proposed additions)

- o Single building or buildings connected with enclosed corridors = 2
- o Well organized campus plan, buildings connected with covered walks, interior corridors = 1
- o Multiple buildings, not connected, some exterior corridors = 0

0

E. Handicapped Accessibility	
o Generally meets state or ADA handicapped code requirements and is suitable for use by physically handicapped persons = 2	
o Needs <u>some</u> modifications to meet handicapped code requirements and to be used satisfactorily by physically handicapped persons = 1	
o Needs <u>substantial</u> modifications to be used satisfactorily by physically handicapped persons (e.g. elevators, lifts, new toilet rooms, etc.) = 0	0
F. Physical Condition of Building - (structural, roof, exterior walls, windows, doors, interior partitions , ceilings , flooring)	
o Very good condition, only minor repairs required = 4	
o Moderate repairs required, some replacements (e.g.. new windows or roof) =2	
o Structural problems or extensive repairs required, replacement of several systems required (new ceilings, roof, windows, exterior wall repair, moving interior partitions, etc) = 0	0
G. Mechanical and Electrical Systems - (plumbing, heating, air conditioning, electrical service, lighting, telecommunications, fire alarm, computer)	
o Good plumbing, central heating and air conditioning; safe, efficient electrical service and lighting; operable fire alarm and telecommunications = 4	
o Moderate repairs and some replacements required (example: may need new air conditioning or lighting, but plumbing, heating and main electrical service in good condition) = 2	
o Extensive repairs and/or replacement of several systems required = 0	0
H. Hazardous Materials - (asbestos, lead, radon, indoor air quality)	
o Asbestos and other hazardous materials either not present or stabilized = 2	
o Minor problems with hazardous materials, management program in progress = 1	
o Asbestos or other hazardous materials present in building requiring removal = 0	0
Total score (A through H) for building	2

A TOTAL SCORE OF 18 OR MORE INDICATES GOOD FEASIBILITY FOR RENOVATION. A TOTAL SCORE OF 12 OR LESS INDICATES POOR FEASIBILITY FOR RENOVATION. PROCEED WITH SITE ANALYSIS.

II. FEASIBILITY ANALYSIS

II-B. FEASIBILITY ANALYSIS - SITE

A. Site Adequacy - Size of site compared to the N.C. Public School Facility Guidelines.

- o 80% to 100% of current guidelines (or additional land available) = 2
- o 65% to 80% of current guidelines = 1
- o Less than 65% of current guidelines = 0

2

B. Location

- o Near the center of the student population served = 2
- o Important focus of an older neighborhood, 50% or more students live in the neighborhood = 1
- o Not centrally located, most students would be bussed from other areas = 0

2

C. Sewer and Water Systems

- o Municipal or county sewer and water system = 2
- o On-site sewer, adequate for number of students, county water or good well with pressure tank = 1
- o Inadequate on-site sewer system or well = 0

2

D. Parking and Traffic Control

- o Paved drives with auto and bus traffic separated, adequate parking = 2
- o Some paved drives or minor traffic conflicts, not enough parking = 1
- o Bus and autos use same drive or children must cross drives to reach playfields or some buildings or bus and/or auto drop-off on street, limited parking = 0

1

E. Playgrounds and Playfields

- o Ample, well developed playfields, gently sloping, handicapped accessible = 2
- o Limited playfields, well developed, can be made handicapped accessible = 1
- o Very small playfields or located across a street from the school or near a busy street or on a steeply sloping site = 0

2

F. Drainage

- o Good site drainage, no problems = 2
- o Some minor drainage problems, can be corrected economically = 1
- o Drainage problems, standing water on site, would be costly to correct, or in flood plain = 0

1

G. Environmental Problems

- o No environmental problems = 2
- o Minor problems or possibility of minor leaks = 1
- o Leaking fuel tank or contaminated well or problems with sewer system discharge or standing water under building or other major problem = 0

1

Total score (A through G) for site


11

A TOTAL SCORE OF 10 OR MORE INDICATES GOOD SITE FEASIBILITY. A TOTAL SCORE OF 7 OR LESS INDICATES POOR SITE FEASIBILITY .

IF BUILDING FEASIBILITY SCORE IS 18 OR MORE AND SITE FEASIBILITY SCORE IS 10 OR MORE, NO FURTHER ANALYSIS IS REQUIRED (UNLESS YOU CHOOSE TO DO SO). REPLACEMENT OF THESE BUILDINGS SHOULD NOT NORMALLY BE CONSIDERED.

IF BUILDING FEASIBILITY SCORE IS 12 OR LESS AND/OR SITE FEASIBILITY SCORE IS 7 OR LESS, NO FURTHER ANALYSIS IS REQUIRED (UNLESS YOU CHOOSE TO DO SO). REPLACEMENT OF THESE BUILDINGS SHOULD BE CONSIDERED.

PROCEED WITH COST ANALYSIS FOR BUILDINGS WHERE RENOVATION OR REPLACEMENT IS NOT CLEARLY INDICATED BY THE FEASIBILITY STUDY.





PROGRAMMING



Highlights

1. Existing Media Center: 3,500sf. DPI Recommends: 5,000sf.
2. DPI recommends a 2x larger Administration Area.
3. DPI recommends a 2x larger Guidance / Student Support Department.
4. DPI recommends 4x the Staff Support Spaces.




OPTIONS




OPTION 1 – RENOVATION

- Develop a combination of Renovated and New buildings.
- Address all site, program, physical, and code deficiencies.
- Renovate site, exterior, interior, M, E, and P systems.




EXISTING SITE



PHASING
1 BUILDING


16 MONTHS




PHASING

- 1 BUILDING
- 2 INSTALL


16 MONTHS
20 MONTHS



PHASING
1 BUILDING 16 MONTHS
2,3 INSTALL, RELOCATE 20 MONTHS



PHASING
1 BUILDING 16 MONTHS
2, 3, 4 INSTALL, RELOCATE, RENOVATE 20 MONTHS




PHASING		
1	BUILDING	16 MONTHS
2,3,4	INSTALL, RELOCATE, RENOVATE	20 MONTHS
5	RELOCATE + SITEWORK	3 MONTHS




OPTION 1

OPTION 2 – NEW

- Develop a brand new school.
- Fit the school within the existing site, allowing for the entire school to be built at once.



EXISTING SITE



PHASING
1 BUILD


16 MONTHS



PHASING

- 1 BUILD
- 2,3 RELOCATE, DEMOLISH

16 MONTHS
5 MONTHS



PHASING

- 1 BUILD
- 2,3 REMOVE, DEMOLISH
- 4 SITE WORK

- 16 MONTHS
- 5 MONTHS
- 3 MONTHS




OPTION 3 – RENOVATION


- Renovate existing building to extend life of building an additional 15-20 years.

Scope of Work

- New roofing system.
- All new mechanical systems.
- Partially update electrical systems.
- Addition to media center to increase size to meet DPI standards.
- Build 4600sf of permanent classrooms to replace 'Learning Classrooms'.
- Replace exterior windows and repair sills.
- Address site drainage.
- Construct new connector between buildings to provide accessibility.
- Update egress door hardware
- Update toilet rooms to meet ADA.




EXISTING SITE




PHASING
1 RENOVATE, BEGIN BUILDING

5 MONTHS



PHASING

- 1 RENOVATE, BEGIN BUILDING 5 MONTHS
- 2 COMPLETE NEW CONSTRUCTION 3 MONTHS



PHASING

- | | | |
|---|---------------------------|----------|
| 1 | RENOVATE, BEGIN BUILDING | 5 MONTHS |
| 2 | COMPLETE NEW CONSTRUCTION | 3 MONTHS |
| 3 | DEMOLISH, RELOCATE | 1 MONTHS |



BUDGET SUMMARY




Avg. Cost of All School Construction in 2009 ---\$127.92*
Avg. Cost of All School Construction in 2014 --- \$203.00*
Avg. Cost of All School Construction in 2018--- \$????


Represents an increase of **60%** increase in 5 years, 12% per
year, or \$75.00/sf cost increase on average

*Information obtained from NCDPI

Avg. Cost of School Construction




AVG ELEMENTARY SCHOOL COST



Avg cost of an elementary school will jump over 80% from 2009-2020

Elementary School Costs Comparison



Conceptual Budgeting Summary Sheet - Edneyville Elementary

Cost/sf

Option 1					
Grand Total Construction Costs	\$	17,184,783.89		85,000	sf
Overall Project Costs	\$	22,243,588.51			
Length of Project		39 months			
					\$ 202.17

Option 2					
Grand Total Construction Costs	\$	18,791,387.08		85,000	sf
Overall Project Costs	\$	24,187,578.37			
Length of Project		24 months			
					\$ 221.08

Option 3					
Grand Total Construction Costs	\$	7,189,513.98		76,427	sf
Overall Project Costs	\$	9,303,577.90			
Length of Project		9 months			
					\$ 94.07



OPTION 1 – CONCEPTUAL BUDGETING
DETAIL



Conceptual Budgeting - Option 1 - Edneyville Elementary

Phase 1 - Construct New Buildings	23,173	sf	@	\$ 168.00		\$ 3,893,064.00
Escalation-Assumed construction complete by 8/2017	18	month	@	.33% per month	5.940%	\$ 231,248.00

Phase 2 - Install Modular School	1	Village	@	\$ 682,146.67		\$ 682,146.67
Phase 3 - Relocate	3	months				
Phase 4 - Renovate Existing Buildings	61,827	sf	@	\$ 160.00		\$ 9,892,320.00
Escalation-Assumed construction complete by 4/2019	36.5	month	@	.33% per month	12.045%	\$ 1,273,694.51

Phase 5 - Relocate	3	months				
--------------------	---	--------	--	--	--	--

Sub total						\$ 15,972,473.18
Overhead and Profit					6.0%	\$ 958,348.39
Sub total						\$ 16,930,821.57
Bonds and insurance					1.5%	\$ 253,962.32
Grand Total Construction costs						\$ 17,184,783.89

Owner Contingency					8.0%	\$ 1,374,782.71
Soft Costs(AE fees, CM pre-con fee, survey, permitting, geotech, special inspector, material testing agent, Air Monitoring etc.)					12.0%	\$ 2,062,174.07
Commissioning agent					1.0%	\$ 171,847.84
Furniture, fixture, equipment	85,000	sf	@	\$ 10.00		\$ 850,000.00
Technology/ Equipment						\$ 600,000.00
Total Project costs						\$ 22,243,588.51



OPTION 2 – CONCEPTUAL BUDGETING
DETAIL





OPTION 3 – CONCEPTUAL BUDGETING
DETAIL



Conceptual Budgeting - Option 3 - Edneyville Elementary

1 - Construct New Connector, Addition to Media Center, and Classrooms	8,100	sf	@	\$ 168.00		\$ 1,360,800.00
2 - Renovate Existing Building and Site (68,327sf)	1	ls	@	\$ 5,184,650.70		\$ 5,184,650.70
3 - Escalation-Assumed construction complete by 2/2017	8	month	@	.33% per month	2.640%	\$ 136,874.78

Sub total						\$ 6,682,325.48
Overhead and Profit					6.0%	\$ 400,939.53
Sub total						\$ 7,083,265.01
Bonds and insurance					1.5%	\$ 106,248.98
Grand Total Construction costs						\$ 7,189,513.98

Owner Contingency					15.0%	\$ 1,078,427.10
Soft Costs(AE fees, CM pre-con fee, survey, permitting, geotech, special inspector, material testing agent, Air Monitoring etc.)					12.0%	\$ 862,741.68
Commissioning agent					1.0%	\$ 71,895.14
Furniture, fixture, equipment	8,100	sf	@	\$ 10.00		\$ 81,000.00
Technology/ Equipment						\$ 20,000.00
Total Project costs						\$ 9,303,577.90


Turner Creek Elementary School



April 2004	
Capacity	750/950
Cost 2004	\$8,693,010
Cost 2018	\$14,604,256**
sf	80,978


** This school today would have to be upgraded to meet the Energy Code

Turner Creek Elementary School





Turner Creek Elementary School




Guilford County Elementary School




July 2007	
Capacity	750/950
Cost 2007	\$15,350,000
Cost 2018	\$23,639,000
sf	87,000

Guilford County Elementary School



01 FIRST FLOOR PLAN
A1.0 [1]-20



02 LOWER LEVEL FLOOR PLAN
A1.0 [1]-20

03 SCHOOL SIGN
A1.0 [1]-20

KEY	
ROOM NO.	SQ. FT.
ACTUAL SF.	PROGRAMMED SF.

Guilford County Elementary School




Alston Ridge Elementary School



April 2009	
Capacity	810/900
Cost 2009	\$18,112,544
Cost 2018	\$26,082,063
sf	103,806

Abbotts Creek Elementary School




April 2014

Capacity	800/900
Cost 2014	\$17,148,573
Cost 2018	\$20,646,881
sf	112,876



Abbotts Creek Elementary School



NORTH ELEVATION



EAST ELEVATION



WEST ELEVATION



SOUTH ELEVATION



HENDERSONVILLE HIGH SCHOOL





FACILITIES

PROGRAMMING

OPTIONS

BUDGET SUMMARY





FACILITIES



II. FEASIBILITY ANALYSIS

II-A. FEASIBILITY ANALYSIS - BUILDING

Band Building	Cafeteria Building	Classroom Building	Vocational Building	New Gym	Old Gym	Boyd Service	Boyd Showroom
---------------	--------------------	--------------------	---------------------	---------	---------	--------------	---------------

A. Educational Program Adequacy - Typical size of classrooms and other functional spaces compared to the N.C. Public School Facility Guidelines.

- o 85% to 100% of current guidelines = 6
- o 75% to 85% of current guidelines = 3
- o Less than 75% of guidelines or classrooms less than 600 sq.ft. = 0

				6	6		
3	3	3	3				
						0	0

B. Historical or Architectural Significance

- o Listed on the National Historic Register or of significant regional architectural interest = 2
- o Strong local historic interest or sentiment or an example of good school design = 1
- o No particular historical value or architectural interest = 0

		2					
				1	1		
0	0		0			0	0

C. Safety and Code Compliance

- o Generally meets building code requirements (1978 or 1991 code) = 4
- o Needs some modifications in order to meet current bldg. code requirements = 2
- o Needs substantial modifications to meet current building code requirements = 0

2	2		2				
		0		0	0	0	0

D. Relationship to Other Buildings on Site (including proposed additions)

- o Single building or buildings connected with enclosed corridors = 2
- o Well organized campus plan, buildings connected with covered walks, interior corridors = 1
- o Multiple buildings, not connected, some exterior corridors = 0

1	1		1				
		0		0	0	0	0

E. Handicapped Accessibility

- o Generally meets state or ADA handicapped code requirements and is suitable for use by physically handicapped persons = 2
- o Needs some modifications to meet handicapped code requirements and to be used satisfactorily by physically handicapped persons = 1
- o Needs substantial modifications to be used satisfactorily by physically handicapped persons (e.g. elevators, lifts, new toilet rooms, etc.) = 0

0	0	0	0	0	0	0	0

F. Physical Condition of Building - (structural, roof, exterior walls, windows, doors, interior partitions, ceilings, flooring)

- o Very good condition, only minor repairs required = 4
- o Moderate repairs required, some replacements (e.g.. new windows or roof) =2
- o Structural problems or extensive repairs required, replacement of several systems required (new ceilings, roof, windows, exterior wall repair, moving interior partitions. etc) = 0

0	0	0	0	0	0	0	0

G. Mechanical and Electrical Systems - (plumbing, heating, air conditioning, electrical service, lighting, telecommunications, fire alarm, computer)

- o Good plumbing, central heating and air conditioning; safe, efficient electrical service and lighting; operable fire alarm and telecommunications = 4
- o Moderate repairs and some replacements required (example: may need new air conditioning or lighting, but plumbing, heating and main electrical service in good condition) = 2
- o Extensive repairs and/or replacement of several systems required = 0

2	2						
		0	0	0	0	0	0

H. Hazardous Materials - (asbestos, lead, radon, indoor air quality)

- o Asbestos and other hazardous materials either not present or stabilized = 2
- o Minor problems with hazardous materials, management program in progress = 1
- o Asbestos or other hazardous materials present in building requiring removal = 0

Total score (A through H) for building

8	8	5	6	7	7	0	0
---	---	---	---	---	---	---	---

A TOTAL SCORE OF 18 OR MORE INDICATES GOOD FEASIBILITY FOR RENOVATION. A TOTAL SCORE OF 12 OR LESS INDICATES POOR FEASIBILITY FOR RENOVATION. PROCEED WITH SITE ANALYSIS.

II. FEASIBILITY ANALYSIS

II-B. FEASIBILITY ANALYSIS - SITE

A. Site Adequacy - Size of site compared to the N.C. Public School Facility Guidelines.

- o 80% to 100% of current guidelines (or additional land available) =2
- o 65% to 80% of current guidelines = 1
- o Less than 65% of current guidelines = 0

2

B. Location

- o Near the center of the student population served =2
- o Important focus of an older neighborhood, 50% or more students live in the neighborhood = 1
- o Not centrally located, most students would be bussed from other areas =0

2

C. Sewer and Water Systems

- o Municipal or county sewer and water system =2
- o On-site sewer, adequate for number of students, county water or good well with pressure tank = 1
- o Inadequate on-site sewer system or well =0

2

D. Parking and Traffic Control

- o Paved drives with auto and bus traffic separated, adequate parking =2
- o Some paved drives or minor traffic conflicts, not enough parking = 1
- o Bus and autos use same drive or children must cross drives to reach playfields or some buildings or bus and/or auto drop-off on street, limited parking = 0

1

- E. Playgrounds and Playfields**
- o Ample, well developed playfields, gently sloping, handicapped accessible =
 - o Limited playfields, well developed, can be made handicapped accessible =
 - o Very small playfields or located across a street from the school or near a busy street or on a steeply sloping site =

- F. Drainage**
- o Good site drainage, no problems =
 - o Some minor drainage problems, can be corrected economically =
 - o Drainage problems, standing water on site, would be costly to correct, or in flood plain =

- G. Environmental Problems**
- o No environmental problems =
 - o Minor problems or possibility of minor leaks =
 - o Leaking fuel tank or contaminated well or problems with sewer system discharge or standing water under building or other major problem =



Total score (A through G) for site

A TOTAL SCORE OF 10 OR MORE INDICATES GOOD SITE FEASIBILITY. A TOTAL SCORE OF 7 OR LESS INDICATES POOR SITE FEASIBILITY .

IF BUILDING FEASIBILITY SCORE IS 18 OR MORE AND SITE FEASIBILITY SCORE IS 10 OR MORE, NO FURTHER ANALYSIS IS REQUIRED (UNLESS YOU CHOOSE TO DO SO). REPLACEMENT OF THESE BUILDINGS SHOULD NOT NORMALLY BE CONSIDERED.

IF BUILDING FEASIBILITY SCORE IS 12 OR LESS AND/OR SITE FEASIBILITY SCORE IS 7 OR LESS, NO FURTHER ANALYSIS IS REQUIRED (UNLESS YOU CHOOSE TO DO SO). REPLACEMENT OF THESE BUILDINGS SHOULD BE CONSIDERED.

PROCEED WITH COST ANALYSIS FOR BUILDINGS WHERE RENOVATION OR REPLACEMENT IS NOT CLEARLY INDICATED BY THE FEASIBILITY STUDY.





PROGRAMMING



Highlights

1. Existing Gross SF: 132,000sf. DPI Recommends: 150,000sf.
2. Correct # of classrooms, but they should be 25% larger.
3. Theater Arts program is 30% larger than required.
4. Existing Media Center: 2150sf. DPI Recommends: 10,000sf.
5. Physical Education Program is 50% larger than the DPI standard.
6. DPI recommends 2x the Administration Area.
7. DPI recommends a 4x larger Guidance / Student Support Department.



OPTIONS



OVERALL GOALS:

- Minimize length of construction
 - Thoughtfully stage the work
 - Maintain continuity of programs
 - Minimize number of moves
-
- Work with existing topography
 - Maintain existing track and it's perimeter
 - Integrate vehicular access and parking
-
- Optimize program adjacencies
 - Create a beautiful campus
 - Honor the existing classroom building
 - Meet 21st century demands

OVERALL GOALS:

- Minimize length of construction
- Thoughtfully stage the work
- Maintain continuity of programs
- Minimize number of moves

- **Work with existing topography**
- **Maintain existing track and it's perimeter**
- **Integrate vehicular access and parking**

- Optimize program adjacencies
- Create a beautiful campus
- Honor the existing classroom building
- Meet 21st century demands

OVERALL GOALS:


- Minimize length of construction
- Thoughtfully stage the work
- Maintain continuity of programs
- Minimize number of moves

- Work with existing topography
- Maintain existing track and it's perimeter
- Integrate vehicular access and parking

- Optimize program adjacencies
- Create a beautiful campus
- Honor the existing classroom building
- Meet 21st century demands


OPTION 1- MAX/MIN

- **Renovation with Maximum amount of gain with Minimal New Work**
- Address Program Deficiencies
- Meet Minimum DPI Standards
- Address Physical Deficiencies of the Existing construction
- New M,E,P Systems.
- Address Building Code Compliance



OPTION 1


INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
Yes	Not for 1.5 Years	2	39 Months (5/2020)	Yes, for 32 months



OPTION 1

PHASING

1 PREPARE THE NORTH SITE




OPTION 1

PHASING

1,2 PREPARE THE NORTH SITE

3 MONTHS



OPTION 1

PHASING

- 1,2 PREPARE THE NORTH SITE
- 3 RELOCATE

3 MONTHS




OPTION 1

PHASING

- 1,2 PREPARE THE NORTH SITE
- 3,4 RELOCATE, RENOVATE AND BUILD


3 MONTHS



OPTION 1

PHASING


- 1,2** PREPARE THE NORTH SITE 3 MONTHS
- 3,4,5** RELOCATE, RENOVATE AND BUILD, RELOCATE 18 MONTHS



OPTION 1

PHASING

- | | | |
|--------------------------------|---|----------------------------------|
| <p>1,2</p> <p>3,4</p> <p>6</p> | <p>PREPARE THE NORTH SITE</p> <p>RELOCATE, RENOVATE AND BUILD, RELOCATE</p> <p>RELOCATE</p> | <p>3 MONTHS</p> <p>18 MONTHS</p> |
|--------------------------------|---|----------------------------------|



OPTION 1

PHASING


1,2	PREPARE THE NORTH SITE	3	MONTHS
3,4	RELOCATE, RENOVATE AND BUILD, RELOCATE	18	MONTHS
6,7	RELOCATE, DEMOLISH		



OPTION 1

PHASING


- | | | | |
|-------|--|----|--------|
| 1,2 | PREPARE THE NORTH SITE | 3 | MONTHS |
| 3,4 | RELOCATE, RENOVATE AND BUILD, RELOCATE | 18 | MONTHS |
| 6,7,8 | RELOCATE, DEMOLISH, BUILD | | |



OPTION 1

PHASING


1,2	PREPARE THE NORTH SITE	3	MONTHS
3,4	RELOCATE, RENOVATE AND BUILD, RELOCATE	18	MONTHS
6,7,8,9	RELOCATE, DEMOLISH, BUILD, AND RELOCATE	14	MONTHS



OPTION 1

PHASING

1,2	PREPARE THE NORTH SITE	3	MONTHS
3,4	RELOCATE, RENOVATE AND BUILD, RELOCATE	18	MONTHS
6, 7, 8, 9	RELOCATE, DEMOLISH, BUILD, AND RELOCATE	14	MONTHS
10	SITework	4	MONTHS
	TOTAL	39	MONTHS




OPTION 1

INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
Yes	Not for 1.5 Years	2	39 Months (5/2020)	Yes, for 32 months


OPTION 2 – ORIGINAL AND NEW

- Keep the character of the original building, and build all else new.
- Address all program, physical, and code deficiencies.



OPTION 2

INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
Yes	Throughout	2	47 Months (1/2021)	Yes, for 21 months




OPTION 2

PHASING

1 PREPARE THE NORTH SITE

3 MONTHS




OPTION 2

PHASING

- 1** PREPARE THE NORTH SITE
- 2** BUILD

- 3** MONTHS
- 17** MONTHS




OPTION 2

PHASING

1 PREPARE THE NORTH SITE
2,3 BUILD, RELOCATE


3 3 MONTHS
17 17 MONTHS



OPTION 2

PHASING

- | | | | |
|-----|------------------------|----|--------|
| 1 | PREPARE THE NORTH SITE | 3 | MONTHS |
| 2,3 | BUILD, RELOCATE | 17 | MONTHS |
| 4 | DEMOLISH | 21 | MONTHS |




OPTION 2

PHASING

1 PREPARE THE NORTH SITE
2,3 BUILD, RELOCATE
4,5 DEMOLISH, INSTALL


3 MONTHS
17 MONTHS
21 MONTHS



OPTION 2

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6	DEMOLISH, INSTALL, RELOCATE	21	MONTHS



OPTION 2

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6, 7	DEMOLISH, INSTALL, RELOCATE, BUILD + RENOVATE	21	MONTHS



OPTION 2

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6, 7	DEMOLISH, INSTALL, RELOCATE, BUILD + RENOVATE	21	MONTHS
8	RELOCATE	6	MONTHS



OPTION 2

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6, 7	DEMOLISH, INSTALL, RELOCATE, BUILD + RENOVATE	21	MONTHS
8,9	RELOCATE, DEMOLISH	6	MONTHS



OPTION 2

PHASING

1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6, 7	DEMOLISH, INSTALL, RELOCATE, BUILD + RENOVATE	21	MONTHS
8, 9, 10	RELOCATE, DEMOLISH, SITEWORK	6	MONTHS




OPTION 2

INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
Yes	Throughout	2	47 Months (1/2021)	Yes, for 21 months


OPTION 2a – ORIGINAL AND NEW

- Keep the character of the original building, and build all else new.
- Address all program, physical, and code deficiencies.



OPTION 2a

INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
Yes	Always	3	60 Months (3/2022)	No




OPTION 2a

PHASING

1 PREPARE THE NORTH SITE

3 MONTHS



- PHYS ED
 - MEDIA
 - DINING


2

OPTION 2a

PHASING

- 1 PREPARE THE NORTH SITE
- 2 BUILD

- 3 MONTHS
- 17 MONTHS




OPTION 2a

PHASING

1 PREPARE THE NORTH SITE
2,3 BUILD, RELOCATE


3 MONTHS
17 MONTHS



OPTION 2a

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4	DEMOLISH	21	MONTHS



OPTION 2a

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4,5	DEMOLISH, BUILD	18	MONTHS



OPTION 2a

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6	DEMOLISH, BUILD, RELOCATE	21	MONTHS



OPTION 2a

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6	DEMOLISH, INSTALL, RELOCATE	21	MONTHS
7	RENOVATE	19	MONTHS



OPTION 2a

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6	DEMOLISH, INSTALL, RELOCATE	21	MONTHS
7, 8	RENOVATE, RELOCATE	19	MONTHS



OPTION 2a

PHASING


1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6	DEMOLISH, INSTALL, RELOCATE	21	MONTHS
7, 8, 9	RENOVATE, RELOCATE, DEMOLISH	19	MONTHS



OPTION 2a

PHASING

1	PREPARE THE NORTH SITE	3	MONTHS
2,3	BUILD, RELOCATE	17	MONTHS
4, 5, 6	DEMOLISH, INSTALL, RELOCATE	21	MONTHS
7, 8, 9, 10	RENOVATE, RELOCATE, DEMOLISH, SITEWORK	19	MONTHS




OPTION 2a

INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
Yes	Always	3	60 Months (3/3022)	No


OPTION 3 – ALL NEW BUILDINGS

- Develop a brand new school.
- Fit the school within the 'Boyd Site' footprint, allowing for the entire school to be built at once.
- Suggest a future use for the original classroom building.



OPTION 3


INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
No	Always	1	32 Months (10/2019)	No



OPTION 3

PHASING

- 1** PREPARE THE NORTH SITE 3 MONTHS




OPTION 3

PHASING

- 1** PREPARE THE NORTH SITE
- 2** CONSTRUCT

3 MONTHS
21 MONTHS




OPTION 3

PHASING

- 1** PREPARE THE NORTH SITE
- 2** CONSTRUCT
- 3** RELOCATE


3 MONTHS
21 MONTHS



OPTION 3

PHASING


1	PREPARE THE NORTH SITE	3 MONTHS
2	CONSTRUCT	21 MONTHS
3,4	RELOCATE, DEMOLISH	3 MONTHS



OPTION 3

PHASING

1	PREPARE THE NORTH SITE	3 MONTHS
2	CONSTRUCT	21 MONTHS
3,4	RELOCATE, DEMOLISH	3 MONTHS
5	SITework	5 MONTHS
	TOTAL	32 MONTHS




OPTION 3

INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
No	Always	1	32 Months (10/2019)	No


OPTION 4 – RENOVATION AND NEW

- Develop a combination of renovated and new buildings.
- Keep buildings which have character.
- Create a tighter overall campus.



OPTION 4

INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
Yes	Not for 1.5 Years	2	44 Months (10/2020)	Yes, for 36 months



OPTION 4

PHASING

1,2 PREPARE THE NORTH SITE

3 MONTHS




OPTION 4

PHASING

1,2 PREPARE THE NORTH SITE

3 MONTHS



OPTION 4

PHASING

1, 2 PREPARE THE NORTH SITE
3, 4, 5 RELOCATE, DEMOLISH, BUILD

3 MONTHS
18 MONTHS




OPTION 4

PHASING

- 1, 2 PREPARE THE NORTH SITE
- 3, 4, 5 RELOCATE, DEMOLISH, BUILD

- 3 MONTHS
- 18 MONTHS




OPTION 4

PHASING

- 1, 2** PREPARE THE NORTH SITE
- 3, 4, 5** RELOCATE, DEMOLISH, BUILD


3 MONTHS
18 MONTHS



OPTION 4

PHASING


- | | | | |
|-------------------|---|-----------|---------------|
| 1, 2 | PREPARE THE NORTH SITE | 3 | MONTHS |
| 3, 4, 5 | RELOCATE, DEMOLISH, BUILD | 18 | MONTHS |
| 6, 7, 8, 9 | RELOCATE, INSTALL, DEMOLISH, BUILD | 18 | MONTHS |



OPTION 4

PHASING


- | | | | |
|------------|------------------------------------|----|--------|
| 1, 2 | PREPARE THE NORTH SITE | 3 | MONTHS |
| 3, 4, 5 | RELOCATE, DEMOLISH, BUILD | 18 | MONTHS |
| 6, 7, 8, 9 | RELOCATE, INSTALL, DEMOLISH, BUILD | 18 | MONTHS |



OPTION 4

PHASING


- | | | | |
|-------------------|---|-----------|---------------|
| 1, 2 | PREPARE THE NORTH SITE | 3 | MONTHS |
| 3, 4, 5 | RELOCATE, DEMOLISH, BUILD | 18 | MONTHS |
| 6, 7, 8, 9 | RELOCATE, INSTALL, DEMOLISH, BUILD | 18 | MONTHS |



OPTION 4

PHASING


- | | | | |
|-------------------|---|-----------|---------------|
| 1, 2 | PREPARE THE NORTH SITE | 3 | MONTHS |
| 3, 4, 5 | RELOCATE, DEMOLISH, BUILD | 18 | MONTHS |
| 6, 7, 8, 9 | RELOCATE, INSTALL, DEMOLISH, BUILD | 18 | MONTHS |



OPTION 4

PHASING


1, 2	PREPARE THE NORTH SITE	3	MONTHS
3, 4, 5	RELOCATE, DEMOLISH, BUILD	18	MONTHS
6, 7, 8, 9	RELOCATE, INSTALL, DEMOLISH, BUILD	18	MONTHS
10	RELOCATE, SITEWORK	5	MONTHS
TOTAL		44	MONTHS



OPTION 4

PHASING

1, 2	PREPARE THE NORTH SITE	3	MONTHS
3, 4, 5	RELOCATE, DEMOLISH, BUILD	18	MONTHS
6, 7, 8, 9	RELOCATE, INSTALL, DEMOLISH, BUILD	18	MONTHS
10, 11	RELOCATE, SITEWORK	5	MONTHS
	TOTAL	44	MONTHS



OPTION 4

INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
Yes	Not for 1.5 Years	2	44 Months (10/2020)	Yes, for 36 months

Option	INCORPORATE EXISTING	GYMNASIUM ON CAMPUS	# NEW BLDG. PHASES	LENGTH CONSTRUCTION	MODULAR VILLAGE
1	Yes	Not for 1.5 Years	2	32 Months (5/2020)	Yes, for 32 Months
2	Yes	Throughout	2	47 Months (1/2021)	Yes, for 21 Months
2A	Yes	Throughout	3	60 Months (3/2022)	No
3	No	Throughout	1	32 Months (10/2019)	No
4	Yes	Not for 1.5 Years	2	44 Months (10/2020)	Yes, for 36 months






BUDGET SUMMARY



AVERAGE HIGH SCHOOL COST



Avg cost of a high school school will jump over 70% from 2010-2020

Conceptual Budgeting Summary Sheet - Hendersonville High

Cost/Sf

Option 1					
Grand Total Construction Costs	\$	42,832,048.15	161,500	sf	\$ 265.21
Overall Project Costs	\$	54,041,778.26			
Length of Project		39 months			

\$4.50 Million Escalation
\$2.09 Million Modular Village

Option 2					
Grand Total Construction Costs	\$	43,364,995.38	161,500	sf	\$ 268.51
Overall Project Costs	\$	52,612,694.55			
Length of Project		47 months			

\$5.25 Million Escalation
\$0.85 Million Modular Village

Option 2a					
Grand Total Construction Costs	\$	47,132,852.16	181,500	sf	\$ 259.69
Overall Project Costs	\$	57,218,765.55			
Length of Project		60 months			

\$6.51 Million Escalation

Option 3					
Grand Total Construction Costs	\$	41,491,744.34	161,500	sf	\$ 256.91
Overall Project Costs	\$	50,402,258.32			
Length of Project		32 months			

\$3.89 Million Escalation

Option 4					
Grand Total Construction Costs	\$	44,378,356.00	161,500	sf	\$ 274.79
Overall Project Costs	\$	53,808,460.08			
Length of Project		44 months			

\$5.15 Million Escalation
\$1.73 Million Modular Village



OPTION 1 – CONCEPTUAL BUDGETING
DETAIL



Conceptual Budgeting - Option 1 - Hendersonville High

Phase 1 - Clear and Prepare the Site	3.8	acres	@	\$ 250,000.00		\$ 947,021.35
Escalation-Assumed construction complete by 5/2017	20.0	month	@	.37% per month	7.400%	\$ 70,079.58

Phase 2 - Install Modular School	1	Village	@	\$ 2,089,626.67		\$ 2,089,626.67
Escalation-Assumed construction complete by 5/2017	20.0	month	@	.37% per month	7.400%	\$ 154,632.37

Phase 3 - Relocate	2	months				
Phase 4 - Renovate Existing Buildings	77,487	sf	@	\$ 190.00		\$ 14,722,530.00
Phase 4 - Construct New Buildings	16,476	sf	@	\$ 198.00		\$ 3,262,248.00
Phase 4 - Sitework	2	acres	@	\$ 250,000.00		\$ 500,000.00
Phase 5 - Relocate	3	months				
Escalation-Assumed construction complete by 11/2018	29.0	month	@	.37% per month	10.730%	\$ 1,983,416.68

Phase 6 - Relocate	2	months				
Phase 7 - Demolish Existing Old Gym	27,120	sf	@	\$ 7.00		\$ 189,840.00
Phase 8 - Renovate Existing Buildings	34,573	sf	@	\$ 190.00		\$ 6,568,870.00
Phase 8 - Construct New Buildings	32,964	sf	@	\$ 198.00		\$ 6,526,872.00
Phase 8 - Sitework	2	acres	@	\$ 200,000.00		\$ 300,000.00
Phase 9 - Relocate	3	months				
Phase 10 - Sitework	4	acres	@	\$ 50,000.00		\$ 200,000.00
Escalation-Assumed construction complete by 5/2020	45.0	month	@	.37% per month	16.650%	\$ 2,295,299.40

Sub total						\$ 39,810,436.05
Overhead and Profit					6.0%	\$ 2,388,626.16
Sub total						\$ 42,199,062.22
Bonds and insurance					1.5%	\$ 632,985.93
Grand Total Construction costs						\$ 42,832,048.15

Owner Contingency					8.0%	\$ 3,426,563.85
Soft Costs(AE fees, CM pre-con fee, survey, permitting, geotech, special inspector, material testing agent, Air Monitoring etc.)					12.0%	\$ 5,139,845.78
Commissioning agent					1.0%	\$ 428,320.48
Furniture, fixture, equipment	161,500	sf	@	\$ 10.00		\$ 1,615,000.00
Technology/ Equipment						\$ 600,000.00
Total Project costs						\$ 54,041,778.26



OPTION 2 – CONCEPTUAL BUDGETING
DETAIL



Conceptual Budgeting - Option 2 - Hendersonville High

Phase 1 - Clear and Prepare the Site	3.8	acres	@	\$ 300,000.00		\$ 1,136,425.62
Escalation-Assumed construction complete by 5/2017	20.0	month	@	.37% per month	7.400%	\$ 84,095.50

Phase 2 - Construct the new Phys Ed, Media, Dining Facility	58,000	sf	@	\$ 205.00		\$ 11,890,000.00
Phase 3 - Relocate	2	months				
Escalation-Assumed construction complete by 10/2018	28.5	month	@	.37% per month	10.545%	\$ 1,253,800.50

Phase 4 - Demolish Existing Buildings	61,693	sf	@	\$ 7.00		\$ 431,851.00
Phase 5 - Install Modular School	1	Village	@	\$ 852,683.33		\$ 852,683.33
Phase 6 - Relocate	2	months				
Phase 7 - Renovate Existing Building	59,487	sf	@	\$ 190.00		\$ 11,302,530.00
Phase 7 - Construct New Buildings	44,013	sf	@	\$ 194.00		\$ 8,538,522.00
Escalation-Assumed construction complete by 7/2020	47.5	month	@	.37% per month	17.575%	\$ 3,712,821.80

Phase 8 - Relocate	2	months				
Phase 9 - Demolish Existing Vocational	21,420	sf	@	\$ 7.00		\$ 149,940.00
Phase 10 - Remaining Sitework	3	acres	@	\$ 250,000.00		\$ 750,000.00
Escalation-Assumed construction complete by 1/2121	61.0	month	@	.37% per month	22.570%	\$ 203,116.46

Sub total						\$ 40,305,786.21
Overhead and Profit					6.0%	\$ 2,418,347.17
Sub total						\$ 42,724,133.38
Bonds and insurance					1.5%	\$ 640,862.00
Grand Total Construction costs						\$ 43,364,995.38

Owner Contingency					5.0%	\$ 2,168,249.77
Soft Costs(AE fees, CM pre-con fee, survey, permitting, geotech, special inspector, material testing agent, Air Monitoring etc.)					12.0%	\$ 5,203,799.45
Commissioning agent					1.0%	\$ 433,649.95
Furniture, fixture, equipment	161,500	sf	@	\$ 8.00		\$ 1,292,000.00
Technology/ Equipment						\$ 150,000.00
Total Project costs						\$ 52,612,694.55



OPTION 2A – CONCEPTUAL BUDGETING
DETAIL



Conceptual Budgeting - Option 2a - Hendersonville High

Phase 1 - Clear and Prepare the Site	3.8	acres	@	\$ 300,000.00		\$ 1,136,425.62
Escalation-Assumed construction complete by 5/2017	20.0	month	@	.37% per month	7.400%	\$ 84,095.50

Phase 2 - Construct the new Phys Ed, Media, Dining Facility	58,000	sf	@	\$ 205.00		\$ 11,890,000.00
Phase 3 - Relocate	2	months				
Escalation-Assumed construction complete by 10/2018	28.5	month	@	.37% per month	10.545%	\$ 1,253,800.50

Phase 4 - Demolish Existing Buildings	61,693	sf	@	\$ 7.00		\$ 431,851.00
Phase 5 - Construct New Buildings	60,000	sf	@	\$ 194.00		\$ 11,640,000.00
Phase 6 - Relocate	2	months				
Escalation-Assumed construction complete by 7/2020	47.5	month	@	.37% per month	17.575%	\$ 2,121,627.81

Phase 7 - Renovate Existing Building	59,487	sf	@	\$ 190.00		\$ 11,302,530.00
Phase 8 - Relocate	2	months				
Phase 9 - Demolish Existing Vocational	21,420	sf	@	\$ 7.00		\$ 149,940.00
Phase 10 - Remaining Sitework	3	acres	@	\$ 250,000.00		\$ 750,000.00
Escalation-Assumed construction complete by 3/2023	67.5	month	@	.37% per month	24.975%	\$ 3,047,566.88

Sub total						\$ 43,807,837.31
Overhead and Profit					6.0%	\$ 2,628,470.24
Sub total						\$ 46,436,307.55
Bonds and insurance					1.5%	\$ 696,544.61
Grand Total Construction costs						\$ 47,132,852.16

Owner Contingency					5.0%	\$ 2,356,642.61
Soft Costs(AE fees, CM pre-con fee, survey, permitting, geotech, special inspector, material testing agent, Air Monitoring etc.)					12.0%	\$ 5,655,942.26
Commissioning agent					1.0%	\$ 471,328.52
Furniture, fixture, equipment	181,500	sf	@	\$ 8.00		\$ 1,452,000.00
Technology/ Equipment						\$ 150,000.00
Total Project costs						\$ 57,218,765.55



OPTION 3 – CONCEPTUAL BUDGETING
DETAIL



Conceptual Budgeting - Option 3 - Hendersonville High

Phase 1 - Clear and Prepare the Site	3.8	acres	@	\$ 300,000.00		\$ 1,136,425.62
Escalation-Assumed construction complete by 5/2017	20	month	@	.37% per month	7.400%	\$ 84,095.50

Phase 2 - Construct the new Facility	161,500	sf	@	\$ 198.00		\$ 31,977,000.00
Phase 2 - Sitework	4	acres	@	\$ 100,000.00		\$ 380,000.00
Escalation-Assumed construction complete by 2/2019	30.5	month	@	.37% per month	11.285%	\$ 3,608,604.45

Phase 3 - Relocate	3	months				
Phase 4 - Demolish Existing Buildings	83,113	sf	@	\$ 7.00		\$ 581,791.00
Phase 5 - Sitework	3	acres	@	\$ 200,000.00		\$ 600,000.00
Escalation-Assumed construction complete by 10/2019	45	month	@	.37% per month	16.650%	\$ 196,768.20

Sub total						\$ 38,564,684.77
Overhead and Profit					6.0%	\$ 2,313,881.09
Sub total						\$ 40,878,565.85
Bonds and insurance					1.5%	\$ 613,178.49
Grand Total Construction costs						\$ 41,491,744.34

Owner Contingency					5.0%	\$ 2,074,587.22
Soft Costs(AE fees, CM pre-con fee, survey, permitting, geotech, special inspector, material testing agent, Air Monitoring etc.)					12.0%	\$ 4,979,009.32
Commissioning agent					1.0%	\$ 414,917.44
Furniture, fixture, equipment	161,500	sf	@	\$ 8.00		\$ 1,292,000.00
Technology/ Equipment						\$ 150,000.00
Total Project costs						\$ 50,402,258.32



OPTION 4 – CONCEPTUAL BUDGETING
DETAIL



Conceptual Budgeting - Option 4 - Hendersonville High

Phase 1 - Clear and Prepare the Site	3.8 acres	@	\$ 300,000.00		\$ 1,136,425.62
Escalation-Assumed construction complete by 5/2017	20 month	@	.37% per month	7.400%	\$ 84,095.50

Phase 2 - Install Modular School	1 Village	@	\$ 1,044,813.33		\$ 1,044,813.33
Escalation-Assumed construction complete by 5/2017	20 month	@	.37% per month	7.400%	\$ 77,316.19

Phase 3 - Relocate	2 months				
Phase 4 - Demolish Existing Buildings	54,373 sf	@	\$ 7.00		\$ 380,611.00
Phase 5 - Construct New Phys Ed Buildings	28,000 sf	@	\$ 205.00		\$ 5,740,000.00
Phase 5 - Construct New Buildings	32,000 sf	@	\$ 194.00		\$ 6,208,000.00
Escalation-Assumed construction complete by 11/2018	29 month	@	.37% per month	10.730%	\$ 1,322,859.96


Phase 6 - Relocate	2 months				
Phase 7 - Install Modular School	1 Village	@	\$ 682,146.67		\$ 682,146.67
Phase 8 - Demolish Existing Buildings	28,740 sf	@	\$ 7.00		\$ 201,180.00
Phase 9 - Renovate Existing Building	59,487 sf	@	\$ 190.00		\$ 11,302,530.00
Phase 9 - Construct New Buildings	42,013 sf	@	\$ 194.00		\$ 8,150,522.00
Phase 9 - Sitework	2 acres	@	\$ 250,000.00		\$ 500,000.00
Phase 10 - Relocate	3 months				
Escalation-Assumed construction complete by 5/2020	47 month	@	.37% per month	17.390%	\$ 3,504,820.94

Phase 11 - Remaining Sitework	3 acres	@	\$ 250,000.00		\$ 750,000.00
Escalation-Assumed construction complete by 10/2020	58.5 month	@	.37% per month	21.645%	\$ 162,337.50

Sub total					\$ 41,247,658.71
Overhead and Profit				6.0%	\$ 2,474,859.52
Sub total					\$ 43,722,518.23
Bonds and insurance				1.5%	\$ 655,837.77
Grand Total Construction costs					\$ 44,378,356.00

Owner Contingency				5.0%	\$ 2,218,917.80
Soft Costs(AE fees, CM pre-con fee, survey, permitting, geotech, special inspector, material testing agent, Air Monitoring etc.)				12.0%	\$ 5,325,402.72
Commissioning agent				1.0%	\$ 443,783.56
Furniture, fixture, equipment	161,500 sf	@	\$ 8.00		\$ 1,292,000.00
Technology/ Equipment					\$ 150,000.00
Total Project costs					\$ 53,808,460.08

PROJECTED ESCALATION



Henderson County Public Schools where tomorrow begins 

Blue Ridge
COMMUNITY COLLEGE

HENDERSON COUNTY - North Carolina -

CLARK NEXSEN

