



Henderson County Capital Projects

100 North King Street, Suite 206

Hendersonville, North Carolina 28792

Addendum #2

Blue Ridge Community College 2022/2023 Patton Bldg Paving Improvements January 5, 2022

This Addendum shall be attached to and made a part of the above named Contract Documents.

The following items are issued to, modify, and clarify the Contract Documents. These items shall have full force and effect as the Contract Documents, and cost involved shall be included in the Bid prices. Bids, to be submitted on the specified date, shall conform to the additions and revisions listed herein.

Acknowledge receipt of the Addendum on the Bid. Failure to do so may subject the bidder to disqualification.

ADDENDUM ITEMS

1. The bid form has been revised to contain/clarify quantities for items number 1,2,5,6 and 7. **The bidder must use the revised bid form when submitting a bid.**
2. The intention of the “single-seal” on the bid form is as follows (in the area designated on Sht. C-100).
The contractor should mill 2-inches, then place the single-seal, then overlay 2-inches over-top of the single-seal. The single-seal is defined as: One single heavy seal of asphalt emulsion followed by one layer of 3/8” seal stone and then compacted.

END OF ADDENDUM #2

BLUE RIDGE COMMUNITY COLLEGE
BRCC 2022/2023 Patton Bldg Paving Improvements
Bid Schedule

Bidder _____

Plans: BRCC 2022/2023 Patton Bldg Paving Improvements

Bids Due:

Receipt of the following **addenda** is hereby acknowledged:

Addendum No.	Addendum Date
1	12.22.2022
2	1.5.2023

No.	DESCRIPTION	UNIT	QTY	UNIT PRICE	TOTAL PRICE
Paving Plan (C-100)					
1	Asphalt Milling 2" Depth	SY	12,774		
2	Asphalt Removal 4" Depth	SY	7,495		
3	Remove Asphalt Curbing	LF	120		
4	Clip Shoulder to Drain	LS	1		
5	Single Seal	SY	12,774		
6	2" Asphalt Overlay (2" S9.5C)	SY	12,774		
7	4" Asphalt Overlay (1.5" S9.5C / 2.5" I19.0B)	SY	7,495		
8	6" Extruded Asphalt Curbing (Machined)	LF	195		
9	Vehicle Paint Striping (Match Existing)	LS	1		
10	Rip-Rap Splash Pad	LS	1		
11	Speed Table	EA	1		
				SUBTOTAL	
Accessible Parking Modifications (C-101)					
12	Demolish & Dispose of Existing Asphalt	SY	795		
13	Tree Removal	LS	1		
14	Silt Fence	LF	311		
15	Reinforced Stabilized Outlet	EA	2		
16	Slope Matting	SY	93		
17	2" Asphalt (S9.5C)	SY	777		
18	8" Compacted ABC Stone	TN	365		
19	6" Extruded Asphalt Curbing (Machined)	LF	108		
20	Accessible Parking Signage	EA	4		
				SUBTOTAL	
Generic Parking Striping Plan (C-104)					
21	Parking Lot Striping	LS	1		
				SUBTOTAL	
Performance & Payment Bonds					
22	Performance & Payment Bonds	LS	1		
				SUBTOTAL	

Alternate #1				
Driving Course Striping Plan (C-103)				
23	Stripe Surveying & Layout	LS	1	_____
24	Course Striping	LS	1	_____
SUBTOTAL				_____
Alternate #2				
25	Increase for 2 Phase Construction (Incl. Traffic Control)	LS	1	_____
	Indicate increased number of construction days: _____			_____
SUBTOTAL				_____
Alternate #3				
26	Deduct For Contract Extension to May 31, 2023	LS	1	_____
SUBTOTAL				_____

Paving Plan (Items #1-11) _____
Accessible Parking Modifications (#12-20) _____
Generic Parking Striping Plan (#21) _____
Performance & Payment Bonds (#22) _____

TOTAL BASE BID _____

Add Alternate #1 - Driving Course Striping Plan (#23-24) _____

Add Alternate #2 - Phased Construction (#25) _____

Add Alternate #3 - Phased Construction (#26) _____

TOTAL ALTERNATES _____

GRAND TOTAL _____

NCDOT Asphalt Index at Time of Bid _____

Anticipated Construction Duration _____

NOTES:

- 1 Price for patching including asphalt removal should include disposal of waste material off site at an approved location.
- 2 **All items quantities are approximate & shall be verified by contractor prior to bidding.**
- 3 The Owner will be responsible for all testing.
- 4 NCDOT standards shall apply to all work.
- 5 All proposed paint striping shall be two (2) coats of asphalt paint.

Submitted by:

Date:

Address

License Number

Seal (if applicable)

List of Subcontractors: _____